## BANGALORE DIVISION.

*Notification, dated 22nd May* 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 12th June 1933, for "Restoring Misiganahalli Minor Tank Reg. No. 195 of Devanhalli Taluk." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Bangalore Division, Bangalore, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. They should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 as earnest money, and be superscribed "Tender for Restoring Misiganahalli Minor Tank Reg. No. 195 of Devanhalli Taluk" in default of which, the tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer, Bangalore Division, will be final and legally binding.

12. Quotations must be shown in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotations quoted at so much percentage less or more than estimate rate will not be accepted.

13. Any tender containing a conditional clause contrary to these requirements or making stipulations not provided for either in this advertisement or the abstract quantity will summarily be rejected.

Abstract estimate for Restoring Misiganahalli Minor Tank Reg. No. 195 of Devanhalli Taluk.

| No. | Items of work | Unit | Rate | Quantity | Remarks |
|---|---|---|---|---|---|
| | *Bund R. L. 57·50 top width 4½'.* | | | | |
| 1 | Clearing lantana jungle, cutting grips and trenches and the slopes and top of bund. | Grade | 18 | | |
| 2 | Earthwork to bund including consolidation... | C.yds. | 4,000 | | |
| 3 | New stone revetment ... ... | ,, | 773 | | |
| 4 | Gravel backing ... ... | ,, | 267 | | |
| 5 | Turfing ... ... | S.yds. | 3,217 | | |
| 6 | Grade stones with bed slabs, figuring and painting, etc., complete. | Each | 19 | | |
| 7 | Index stones ... ... | ,, | 19 | | |
| 8 | B. M. stones ... ... | ,, | 2 | | |
| 9 | Gauge stone ... ... | ,, | 1 | | |
| 10 | Register No. and date stone ... ... | ,, | 1 | | |
| 11 | Old stone work with new jelly .. .. | C.yds. | 267 | | |

| No. | Items of work | Unit | Rate | Quantity | Remaks |
|---|---|---|---|---|---|
| | *Constructing a new sluice.* | | | | |
| 1 | Earthwork excavation for foundation .. | C.yds. | 11 | | |
| 2 | Concrete in surki mortar ... ... | C.ft. | 112 | | |
| 3 | Burnt brick in surki mortar ... .. | ,, | 519 | | |
| 4 | Burnt stone slabs 6" thick dressed ... | S.ft. | 189 | | |
| 5 | Plastering with surki mortar .. .. | Sqr. | 3·88 | | |
| 6 | Pointing with suki mortar ... .. | ,, | ·63 | | |
| 7 | Cutting holes in the slabs ... .. | Each | 3 | | |
| 8 | Cutting hole in the orifice slab .. .. ... | ,, | 1 | | |
| | *Left waste weir.* | | | | |
| 1 | Earthwork and forming ramps ... | C.yds. | 32 | | |
| 2 | Stone jelly surki concrete .. ... | C.ft. | 218 | | |
| 3 | Burnt brick in surki mortar ... ... | ,, | 390 | | |
| 4 | Burnt stone slabs 6" thick roughly dressed ... | S.ft. | 111 | | |
| 5 | Plastering with surki mortar ... ... | Sqr. | 3·57 | | |
| 6 | Rough stone work with new jelly wedging ... | C.yds. | 28 | | |
| 7 | Cutting joggle joints .. ... | Each | 8 | | |
| | *Widening and Raising the left waste weir.* | | | | |
| 1 | Earthwork excavation .. | C.yds. | 29 | | |
| 2 | Stone jelly surki concrete ... ... | C.ft. | 225 | | |
| 3 | Burnt brick in surki mortar ... ... | ,, | 1,024 | | |
| 4 | Burnt stone slabs 6" thick roughly dressed ... | S.ft. | 115 | | |
| 5 | Resetting old stone in mortar ... ... | ,, | 112 | | |
| 6 | Plastering with surki mortar ... ,, | Sqr. | 2·89 | | |
| 7 | New rough stone work with jelly packing and wedging. | C.yds. | 22 | | |
| 8 | Resetting old stone with new jelly ... | ,, | 100 | | |
| 9 | Jelly filling below old apron ... ... | ,, | 150 | | |
| 10 | Cutting joggle joints ... .. | No. | 1 | | |
| 11 | Stone jelly surki concrete curved apron abcve the old apron (after reconstructing and jelly packing and wedging). | C.ft. | 750 | | |

H. F. MARKER,
*Executive Engineer.*

## BANGALORE DIVISION.

*Notification No.* 2862, *dated* 22*nd May* 1933.

The portion of the Salem-Bellary Road in Nelamangala Taluk from 8/22 mile to 4/31 mile is closed for fifteen days for all through traffic, on account of a damage to the road in 5/27, Mugalahalli tank bund. The traffic may, however, pass through the loop road passing through Thyamagondlu village starting at 8/22 and joining the main road at 4/31.

H. F. MARKER,
*Executive Engineer.*